THE CORPORATION OF THE Township of Edwardsburgh/Cardinal

Tender for the Jordan Road Culvert Replacement Tender No. EC-PW-24-06

SEALED TENDERS, on the forms supplied with in the Tender Documents, will be received at the Municipal Office Located Spencerville, 18 Centre Street, Spencerville ON, K0E 1X0 UNTIL

Tuesday April 9th, 2024 @ 2:00 pm

In general, the work includes the installation of 3 1800mm CSP culverts.

Major Items Include but Are Not Limited to The Following: 1800 CSP - 46m

Electronic Contract specifications and tender forms may be obtained by emailing the Greer Galloway at <u>kingston@greergalloway.com</u>. Documents will be available Tuesday, March 12, 2024

All inquiries related to the Tender Documents should be directed via email no later than Thursday, April 4th, 2024, at 2:00pm to: <u>kingston@greergalloway.com</u>

Tender documents will be available, for viewing only, at the Township Municipal Office as well as the Greer Galloway office in Kingston.

The tender must be accompanied by an Agreement to Bond or a letter from a financial institution agreeing to supply a letter of credit. Tenders must also include a tender deposit in the form of a Certified Cheque or Bid Bond made payable to the **Township of Edwardsburgh/Cardinal**, in an amount not less than that specified in the Tender Documents.

TENDERS will be opened publicly at the Municipal Office located on 18 Centre Street, in the Town of Spencerville ON. K0E 1X0.

The lowest or any tender will not necessarily be accepted.

Dave Grant, CAO Township of Edwardsburgh/Cardinal

18 Centre Street Spencerville, ON K0E 1X0 T: (613) 658-3055 F: (613) 658-3445 Dsgrant@twpec.ca Mr. Kevin Hawley, P. Eng., Project Manager The Greer Galloway Group Inc. Consulting Engineers

640 Cataraqui Drive, Unit 2A Kingston, ON K7P 2Y5 T: (613) 536-5420 F: (613) 548-3793 Khawley@greergalloway.com

JORDAN ROAD CULVERT REPLACEMENT TOWNSHIP OF EDWARDSBURGH CARDINAL, ON




LIST	OF	DRAWINGS

- C1 PLAN & PROFILE
- D1 DETAILS


APPROXIMATE STRUCTURE LOCATION

THE GREER GALLOWAY GROUP INC. CONSULTING ENGINEERS



PETERBOROUGH BELLEVILLE KINGSTON

640 CATARAQUI WOODS DRIVE, UNIT 2A KINGSTON, ONTARIO K7P 2Y5 PHONE: (613) 536-5420



<text></text>	THE GREER GALLOWAY GROUP INC. CONSULTING ENGINEERS PETERBOROUGH BELLEVILLE KINGSTON BELLEVILLE KINGSTON 640 CATARAQUI WOODS DRIVE #2A KINGSTON, ONTARIO, K7P 2YS PHONE: 613–536–5420 FAX: 613–548–3793 NOTES: 1. ALL WORK SHALL BE IN ACCORDANCE WITH RELEVANT CODES AND GUIDELINES. 2. ALL DRAWINGS AND ADDENDA ARE TO BE READ AS, AND IN CONJUNCTION WITH THE SPECIFICATIONS. 3. ALL EQUIPMENT SHALL BE INSTALLED AS SPECIFIED OR CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS BEFORE PROCEEDING WITH WORK AND BE RESPONSIBLE FOR RESOLUTION BEFORE COMMENCING THE ENGINEER 6. ONTRACTOR MUST REPORT ANY DISCREPANCIES TO ENGINEER FOR RESOLUTION BEFORE COMMENCING THE ENGINEER A DETAIL NO. B DRAWING NO. – WHERE DETAILED IEGEND MA DETAIL NO. RIP RAP COLVERT MATER CULVERT MATER CULVERT MATER CULVERT MATER CULVERT
	SILT FENCE O TURBIDITY CURTAIN -O CONSTRUCTION LIMITS
	APR. 21/21 PROJECT JORDAN ROAD CULVERT REPLACEMENT
	EDWARDSBURGH CARDINAL, ON DRAWING TITLE PLAN & PROFILE 05 04 03
	02 01 ISSUED FOR 100% REVIEW 17/11/23 REVISION DATE DESIGNED BY G. HOEGI
	drawn by S. HIGH
	reviewed by K. HAWLEY
	APPROVED BY K. HAWLEY
	PROJECT DATE 25/09/2023
	(DD/MM/YYY) PROJECT # SCALE 23-5-5392 HOR: 1:250
	VER: 1:50 DRAWING # C1

 otherwise. Prior to construction, Contractor to verify all dimensions, sewer inverts and utility locates and ide possible conflicts. All environmental protection measures are the responsibility of the contractor. Any traffic signs or information signs removed/damaged during construction are to be replaced of the contractors costs. All utility poles to be braced as necessory. The location of utilities is approximate only, and the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove t location of utilities and shall be responsible for adequate protection from damage during construct location of utilities and shall be responsible for adequate protection from damage during construct location of utilities and shall be responsible for adequate protection from damage during construct location of utilities and shall be responsible for adequate protection from damage during construct location of utilities and shall be responsible for adequate protection from damage during construct statistical control/pedestrian signing as per OTM. GRADINC Finished surfaces shall be at a minimum grade of 2% unless otherwise noted. Slopes in landscaped areas shall not exceed 2:1. All existing elevations and grades are to be verified by the contractor prior to grading Utilities are to be located prior to construction All ground surfaces shall be graded to prevent ponding and without low areas except where approximate orachosin outlets are provided. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered on existing surface that has postive drainage down from the raadway. 	<u>(</u>	GEN	ERAL				
 A All environmental protection memoures are the reasonability of the contractor. A wy torffic signs or information signs removed/canaged during construction are to be replaced of the contractor's casts. A all utility over its be broaded as recessary. The inciding of utilities and shall be an environment experiment the contractor middle contractor and the solution of the special base default by repeated by the contractor and the solution of the solution of the solution of the solution of the special base default by the contractor provide during construction of the solution of the	1		Ontario Building Code and, Ontario Provincial Standard Specifications and Drawings unless specified				
 Any inditic signs or information signs removed/damaged during construction are to be replaced of the contractor sould. All utility points to be braced as necessary. The location of utilities is approximate only, and the cased boation should be determined by any information of the control/pedestrian signing as per OTM. CHAIT of control/pedestrian signing as per of the contractor prior to grading CHAIT opposed grades shall be graded to prevent pending and without law areas except where soprosed structures. Chait of the probability of reviewing proposed grades with conflicts regarding the proposed structures. Stopen grade shall be graded at a minimum of 3% until a lower ditah is encountered on existing surface that payted ato applicate granular data to be 100 mm. foranular A and 350mm Gran. B. Provide 38 crossion on subgrade. All actuated areas to be remediated with 100 mm topsoil and seed as per OPS 202 & OPS 202 EX OPS 202 EX OPS 203 at 200 completed. All actuated areas to be remediated with 100 mm topsoil and seed as per OPS 202 & OPS 203 EXEMPT AND EFFOSION CONTROL NOTES All disturbed areas to be interediated with 100 mm topsoil and seed as per OPS 202 & OPS 203 EXEMPT AND EFFOSION CONTROL NOTES All disturbed areas the site where a shall be inspecte after prior to and off	2						
 The contractors casts. All utility poles to be braced as recessory. The location of utilities is approximate and utility companies beneares. The contractor shall be determined by contractor it into dempte during construction. The definition of utilities is approximate and utility companies beneares. The contractor shall be acting construction. TRAFTEL CONTROL The limited surfaces shall be at a minimum grade of 22 unless otherwise noted. Stoces in landscoped areas shall not exceed 2.1. All advating developed areas shall be graded to prevent proving and without los areas exceet where appresses or activation is a responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded to prevent proving and without los areas exceet where appresses or activation is negative drainage away from the roadway. Sub-grade shall be graded at minimum of 35, until a lower dito is an outland. A and 350mm Gran B. Provide 33 creatified analoging away from the roadway. All columbed areas to be remediated with 100 mm topsoil and seed on per OPSS 802 & 0PSS is 2DMINI AAD LEGGON CONTROL MOTES All areasin and addiment control measures and be inspecied after prior to and active and mentioned on the contractor. Any disturbed areas not be conducided with 100 mm topsoil and seed on per OPSS 802 with the astrobel the proposed with excellation. All areasine and baddement control measures and be inspecied after prior to and measures and the estimation of the Contractor on and measures and the estimation. All areasine at the information development of the construction within farty-five (45) days will be prowing the astrobel to active dam	-	3.	All environmental protection measures are the responsibility of the contractor.				
 6. The location of utilities is approximate only, and the accel location phode be determined by the interface of the segmentiate for adequate pretection from damage during construct TEATLE CONTROL 1. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All traffic control/pedestrian signing as per OTM. CRAINE I. All reaction of utilities in the control of the contractor prior to grading I. Utilities are to be located prior to construction I. All organic surfaces shall be graded to privant ponding and without lose areas except where approximate or activabatin outlets are provided. Sub-ornade shall be graded to a minimum of 3%, until a lower ditch is encountered an existing surfaces that has positive drainage away from the readway. STE WORS I. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granular. All disturbed areas to be reemdated with 100 mm topsoil and seed as per OPSS 802 & OPSS as SEDENTI AND FROSIDE CONTROL MOTES All disturbed areas not be headway shall be inspected after prior to and after each noring readures the satisfaction of the graded levers. All be contraction control measures must be removed once as the be approximated on the control of the contract deministration. Control Marking and a seed as per OPSS 802 & OPSS as SEDENTI AND FROSIDE CONTROL MOTES All disturbed areas not scheduled for further construction within forty-five (45) days will be proving the contract deministration. Control measures must be removed	2						
constitution of utilities and subtrottles and utility comparise concerned. The contractor shall prove the root of the second of the dequate protection domage during construct IRAFFIC CONTROL. 1. All traffic control/secentrian signing as per OTM. GRADNO 1. Finished surfaces shall be at a minimum grade of 2% unless otherwise noted. 2. Shoes in landscaped areas shall not exceed 2:1. 3. All costing elevations and grades are to be verified by the contractor prior to grading. 4. Utilities are to be located prior to construction. 6. All grade surfaces shall be graded to prevent ponding and without low areas except where approximate or contractor is responsible for reviewing proposed grades with contractor grading the proposed structures. 7. Sub-grade shall be graded to a minimum of 3%, until a lower ditch is encountered an existing surface shall be graded to area for the rootexy. SITE WORKS 1. All eracits autoproce shall be graded to previous from the rootexy. SITE WORKS 1. All disturbed areas to be nemediated with 100 mm topsoil and social as per OPSS 502 & OPSS 502 SCIENT AND ERGS CONTROL MOTES 1. All eracits and sediment controls shall be inspected offer prior to and attractor and sediment control measures with be inspected offer prior to and attract and sediment control measures with a previous draining-root. 2. All disturbed areas to be remediated with 100 mm topsoil and sed as per OPSS 502 & OPSS 503 SCIENT AND ERGS (DATTOR) MOTES 3. All eraciss and sediment control measures with be inspected offer prior to and attract and minimized on the contract of the Contract Aministrator. 3. All disturbed areas to be control measures within forty-five (45) days will be provide the selection of the Contract Aministrator. 3. All disturbed areas not activated areas and will be inspected offer prior to and attracting control measures within forty-five (45) days will be provide and be exceeded as the shead	Ę	5.	All utility poles to be braced as necessary.				
 All traffic control/podestrian signing as per ON. EXEMPL Initiated surfaces shall be at a minimum grade of 2% unless otherwise noted. Stability elevations and grades are to be verified by the contractor prior to grading. All existing elevations and grades are to be verified by the contractor prior to grading. Utilities are to be located prior to construction. All existing elevations and grades are to be verified by the contractor prior to grading. Julities are to be located prior to construction. Sub-gride shall be graded to prevent panding and without low oreas except where approxement controls is responsible for reversing proposed grades with conflicts regarding the proposed structures. Sub-gride shall be graded at a minimum of 3%, until a lower dich is encountered an existing surface that has positive drainage away from the readway. SUB gride shall be graded compacted granular depths to be 150 mm Granular A and 350mm Grant B. Provide 3% crossful on subgrade. All disturbed oreas to be remediated with 100 mm topsail and seed as per OP55 802 & OP55 802 EXEMPT AND ERGENC CONTROL MOIES All development control measures atable to inspected of the prior to and after each rainfor the basel shall be installed prior to construction and periode and once included of a time veriation. All development control measures atable be inspected after prior to and after each rainfor the satisfaction of the Contract Administrator. All development control measures atable inspected after prior to and after each rainfor the satisfaction or the Contract Administrator. All development control measures atable inspected after prior to and after each rainfor the satisfaction on gradies with a suitable temporat	e		The location of utilities is approximate only, and the exact location should be determined by consulting the municipal authorities and utility companies concerned. The contractor shall prove the location of utilities and shall be responsible for adequate protection from damage during constructi				
CEXDING Finished surfaces shall be at a minimum grade of 2% unless otherwise noted. Stopes in landscaped oreas shall not exceed 21. All existing elevations and grades are to be verified by the contractor prior to grading. Utilities are to be located prior to construction. All grade shall be graded to prevent panding and without low areas except where approximate or activities in euclides are provided. The contractor is responsible for reviewing propased grades with conflicts regarding the propased structures. The contractor is responsible for reviewing propased grades with conflicts regarding the propased structures. Sub-grade shall be graded at a minimum of 3%, until a lower dich is encountered an existing surface that has police drivinge away from the readway. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granue B. Provide 3% createrial on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 80 SEQUENT AND FROSING CONTROL NOTES All erosion and sediment control measures until and active and monitored and monitored and monitored and the evolution of the Contractor throughout the construction and monitored and measures in table temporary much and sed over within secure (7) days of completion. All erosion and sediment control measures to construction within forty—file (45) days will be provided as soon as proceed. Regardiess of site specific lens shoulded on the plans, the Contractor and install erosion control measures to suit the proposed werk mathees to control sediment from running off the site prior on y distance and activation. Regardiess of site specific lens shoulded on the plans, the Contractor and install erosion control measures to suite the proposed werk mathees to control sediment from running off the site prior on y distance on the]	<u>rra</u>	FFIC CONTROL				
 Finished surfaces shall be at a minimum grade of 2% unless otherwise noted. Slopes in landscaped areas shall not exceed 2:1. All existing elevations and grades are to be verified by the contractor prior to grading. Utilities are to be located prior to construction All gradin surfaces shall be graded to prevent panding and without low areas except where approxes elevel of attributes. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded at a minimum of 3%, until a lower dich is encountered on existing surface shall be graded at a minimum of 3%, until a lower dich is encountered on existing surface that has pastive drainage away from the roadway. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Grant B. Provide 3% as creasfill on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 80 SEDMINIT AND EROSION CONTROL NOTES All decision and sediment controls shall be installed prior to construction and monitored and manitared and the astingtion of the Saltowid areas have a removed once site has been stabilized/completed of site works. All erosion and sediment control mesures shall be installed prior to and after each rainfa the satisfaction of the Controck Administrator. Any disturbed areas not achediated for further construction within facty-fine (45) days will be prove with a subgrade. Controck Administrator. All existion and sediment control massares shall be inspected after prior to and after each rainfa the satisfaction of the Controck Administrator. Any disturbed areas not achediated for further construction within facty-fine (45) days will be provide with eached as soons proceed. Following construction, disturbed areas, as well as proposed grassed and vegetate	1	•	All traffic control/pedestrian signing as per OTM.				
 Slopes in landscaped greats shall not exceed 2:1. All existing elevations and grades are to be verified by the contractor prior to grading Utilities are to be located prior to construction All ground surfaces shall be graded to prevent ponding and without low oreas except where approxaves are obtahosin outlets are provided. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered on existing surface that has poollike compacted graduar depths to be 150 mm Granular A and 350mm Gran. Frovide 3% creation on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 80 2% OPSS 80 SEMENT AND ERGININ CONTROL MOTES All dension and sediment controls shall be habiled prior to construction and monitored and monitored and monitored to the proposed verse works. All dension and sediment control measures shall be inspected after prior to and offer each rainfa the subsidized/compreted or site works. All dension and sediment control measures shall be inspected after prior to and offer each rainfa the subsidized/compreted or site works. All ension and sediment control measures shall be inspected after prior to and offer each rainfa the subsidized/compreted or site works. All ension and sediment control measures shall be inspected after prior to and offer each rainfa the subsidized/compreted or site works. All ension and sediment control measures shall be inspected after prior to and offer each rainfa the subsidized/compreted work methods to control measures and usil the provide site works. All ension control measures to subtice therapolate on the proposed grassed and vegetated surfaces, shall reinstruction. Are degrades of site specific items dualided on the plans,	<u>(</u>	GRA	DING				
 All existing elevations and grades are to be verified by the contractor prior to grading Utilities are to be located prior to construction All graund surfaces shall be graded to prevent ponding and without low areas except where approved exceptions is responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered on existing surface that has positive drainage away from the roadway. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered on existing surface that has positive drainage away from the roadway. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granu B. Provide 3% crossfall on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 80 SEDIMENT AND EROSION CONTROL NOTES All erosion and sediment controls shall be installed prior to construction and monitored and mentalized/completed of site works. All erosion and sediment controls measures shall be inspected after prior to and after each rainfor the satisfaction of the Contract Administrator. Ary disturbed creas not scheduled for further construction within forty-five (45) days will be proving with a suitable temporary much and seed cover within sever (7) days of completion. Regardless of site specific litems detailed on the pines, the Contract and infrastrator. Regardless of site specific litems detailed on the pine, the Contract and infrastrator. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall measure used to access the shall be kept clean to the satisfaction of the Director of Public Works. No in water work will be conducted between March 15 – July 15. 	1	•	Finished surfaces shall be at a minimum grade of 2% unless otherwise noted.				
 4. Utilities are to be located prior to construction 5. All ground surfaces shall be graded to prevent ponding and without low areas except where appressed swale or catchbasin outlets are provided. 6. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed structures. 7. Sub-grade shall be graded at a minimum of 3%, until a lower dich is encountered an existing surface that has positive drainage away from the readway. 8. THE WARKS 1. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Grani B. Provide 3% arcasial on subgrade. 2. All disturbed areas to be remediated with 100 mm topsail and seed as per OPSS 802 & OPSS 805 SUBLEMENT AND EROSION CONTROL NOTES 1. All erosion and sediment controls shall be installed prior to construction and monitored and manufaced by the Contractor throughout the construction process, until all disturbed areas nave manufaced by the Contractor throughout the construction process, until all disturbed areas nave satisfized/completed of site works. 2. All deresion and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Manufactor. 3. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide with a suitable temporary much and seed areas notice is administrator. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall related as soon as practical. 6. All roduing the site shall be kept clean to the satisfaction of the Director of Public Works. 7. No in water work will be conducted between March 15 - July 15. 							
 All ground surfaces shall be graded to prevent panding and without low areas except where opport swell or catchboain outlets are provided. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed structures. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered an existing surface that has possible drainage away from the roadway. SITE WORKS Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granu B. Provide 3% crossial on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 805 Section Analytic the construction process, until all disturbed areas have re-vegetated then the temporary sediment and areasin control measures must be removed once site has been stabilized/completed of all works. All erasion and sediment control measures shall be inspected after prior to and after each raining the satisfaction of the Controct Administrator. Any disturbed areas not scheduled for further construction within forty—five (45) days will be provide as soon as practical. All erasion construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall relations to all the proposed to access the site shall be kept clean to the satisfaction of the Director of Public Works. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall relations of well be conducted between March 15 – July 15. No in water work will be conducted between March 15 – July 15. 	5	3.	All existing elevations and grades are to be verified by the contractor prior to grading				
swele or catchbosh outlets are provided. 6. The contractor is responsible for reviewing proposed grades with conflicts regarding the proposed sinculares. 7. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered on existing surface that has positive drainage away from the roadway. SITE WORKS 1. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granu E. Provide 3% crossful on subgrade. 2. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 802 States of the subgrade of the construction process, until all disturbed or and non-intered and monitored and monitored the technology sediment the construction process, until all disturbed or and have a subgrade of site works. 3. All decision and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Administrator. 3. Any disturbed areas not scheduled for further construction within forty-five (45) days will be pro- with a subble temporary much and seed cover within seven (7) days of completion. 4. Regardless of site specific items detailed on the plana, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated of so sound as proceed. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as proctical. 5. Plan work will be conducted between March 15 – July 15. 5. No in water work will be conducted between March 15 – July 15. 5. No in water work will be conducted between March 15 – July 15. 5. No in water work will be conducted between March 15 – July 15. 5. March remain running for the domaine. 5. A discingtion tomain remainer to market and the state and the s							
 structures. Sub-grade shall be graded at a minimum of 3%, until a lower ditch is encountered an existing surface that has positive drainage away from the readway. SIEE WORKS 1. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Granu B. Provide 3% crossfall on subgrade. 2. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 80 SEDIMENT AND EROSION CONTROL NOTES 1. All erosion and sediment controls shall be installed prior to construction and monitored and maintained by the Contractor throughout the construction measures must be removed ance saile has been stabilized/completed of site works. 2. All erosion and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Administrator. 3. Any disturbed areas not scheduled for further construction within server (7) days of completion. 4. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior my disturbance. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as particul. 5. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works. 6. No in water work will be conducted between March 15 – July 15. 	5						
 SUFF WORKS Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Gran. Provide 3% crossful on subgrade. All disturbed areas to be remediated with 100 mm topsoil and seed as per QPSS 802 & QPSS 80 All disturbed areas to be remediated with 100 mm topsoil and seed as per QPSS 802 & QPSS 80 All disturbed areas to be remediated with 100 mm topsoil and seed as per QPSS 802 & QPSS 80 All disturbed areas to be remediated with 100 mm topsoil and seed as per QPSS 802 & QPSS 80 All disturbed areas to a topsoil on and sediment controls shall be installed prior to construction and monitored and maintained by the Contractor throughout the construction process, until all disturbed areas have re-vegetated then the temporary sediment and erosino control measures must be removed once site has been stabilized/completed of site works. All erosion and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Administrator. Any disturbed oreas not scheduled for further construction within forty-five (45) days will be provide und seed cover within seven (7) days of completion. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated to access the site shall be kept clean to the satisfaction of the Director of Public Works. No in water work will be conducted between March 15 - July 15. 	6						
SITE WORKS 1. Where in earth subgrade compacted granular depths to be 150 mm Granular A and 350mm Gran. B. Provide 3% crossfell on subgrade. 2. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS BI <u>SEDIMENT AND EROSION CONTROL NOTES</u> 1. All erosion and sediment controls shall be installed prior to construction and monitored and maintained by the Contractor throughout the construction process, until all disturbed areas have re-vegetated then the temporary sadiment and erosion control measures must be removed once site has been stabilized/completed of site works. 2. All erosion and sediment control measures shall be inspected after prior to and after each rainfo the satisfaction of the Contract Affinistrator. 3. Any disturbed areas not scheduled for further construction within forty—five (45) days will be pro- with a suitable temporary mulch and seed cover within seven (7) days of completion. 4. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior or of disturbance. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. 6. All roads used to access the site shall be kept dean to the satisfaction of the Director of Public Works 7. No in water work will be conducted between March 15 – July 15.	7						
 B. Provide 3% crossfall on subgrade. 2. All disturbed areas to be remediated with 100 mm topsoil and seed as per OPSS 802 & OPSS 80 SEDIMENT AND EROSION CONTROL NOTES 1. All erosion and sediment controls shall be installed prior to construction and monitored and maintained by the Contractor throughout the construction process, until all disturbed areas have re-vegetated then the temporary sediment and erosion control measures must be removed once site has been stabilized/completed of site works. 2. All erosion and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Administrator. 3. Any disturbed areas not scheduled for further construction within forty-five (45) days will be prov with a suitable temporary muich and seed cover within seven (7) days of completion. 4. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. 6. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works 7. No in water work will be conducted between March 15 – July 15. 	с л						
 All disturbed areas to be remediated with 100 mm topsol and seed as per OPSS 802 & OPSS 80 SEDIMENT AND EROSION CONTROL NOTES All erosion and sediment controls shall be installed prior to construction and monitored and monitorided by the Contractor throughout the construction process, until all disturbed areas have re-vegated than the temporry sediment and resolves shall be inspected after prior to and after each rainfa the satisfaction of the Contract Artoninistrator. All erosion and sediment control measures shall be inspected after prior to and ofter each rainfa the satisfaction of the Contract Artoninistrator. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide the satisfaction of the proposed work methods to control sediment from running off the site prior ony disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works No in water work will be conducted between March 15 - July 15. No in water work will be conducted between March 15 - July 15. 	1						
 SEDIMENT AND EROSION CONTROL NOTES All erosion and sediment controls shall be installed prior to construction and monitored and maintained by the Contract throughout the construction process, until all disturbed areas have re-vegetated then the temporary sediment and erosion control measures must be removed once site has been stabilized/completed of site works. All erosion and sediment control measures shall be inspected after prior to and after each roinfa the satisfaction of the Contract Administrator. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide and administrator. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide with a suitable temporary mulch and seed cover within seven (7) days of completion. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works. No in water work will be conducted between March 15 - July 15. 	_						
 All erosion and sediment controls shall be installed prior to construction and monitored and monitored by the Contractor throughout the construction process, until all disturbed areas have re-vegetated then the temporary sediment and erosion control measures must be removed once site has been stabilized/completed of site works. All erosion and sediment control measures shall be inspected after prior to and after each rainfa the satisfaction of the Contract Administrator. Any disturbed areas not scheduled for further construction within forty—five (45) days will be provide and subtraction of the Contract Administrator. Any disturbed areas not scheduled for further construction within forty—five (45) days will be provide and subtraction of the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works. No in water work will be conducted between March 15 – July 15. No in water work will be conducted between March 15 – July 15. No in water work will be conducted between March 15 – July 15. 							
 maintained by the Contractor throughout the construction process, until all disturbed areas have re-vegetated then the temporary sediment and erosion control measures must be removed once site has been stabilized/completed of site works. All erosion and sediment control measures shall be inspected after prior to and after each rainfa the sotisfaction of the Contract Administrator. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide the portage of the site prior and sediment control measures to autit the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works. No in water work will be conducted between March 15 - July 15. No in water work will be conducted between March 15 - July 15. Mores: No in water work will be conducted between March 15 - July 15. More in measure work will be conducted between March 15 - July 15. 							
 the satisfaction of the Contract Administrator. Any disturbed areas not scheduled for further construction within forty-five (45) days will be provide within a suitable temporary mulch and seed cover within seven (7) days of completion. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works No in water work will be conducted between March 15 – July 15. No in water work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. Indefining have work will be conducted between March 15 – July 15. 	I		naintained by the Contractor throughout the construction process, until all disturbed areas have be e—vegetated then the temporary sediment and erosion control measures must be removed once th				
 with a suitable temporary mulch and seed cover within seven (7) days of completion. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works No in water work will be conducted between March 15 – July 15. 	2						
measures to suit the proposed work methods to control sediment from running off the site prior any disturbance. 5. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. 6. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works 7. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. Work work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. No in water work will be conducted between March 15 – July 15. 8. Additional balast may be required depending on local conditions. 8. All dimensions or in millineters unless otherwise shown. 8. Noter State of the millineters unless otherwise shown.	2						
 Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall reinstated as soon as practical. All roads used to access the site shall be kept clean to the satisfaction of the Director of Public Works No in water work will be conducted between March 15 – July 15. Interview work will be conducted between March 15 – July 15. 	4		measures to suit the proposed work methods to control sediment from running off the site prior t				
7. No in water work will be conducted between March 15 – July 15. 7. No in water work will be conducted between March 15 – July 15. Image: Second Condition Work AEA Works Mill be conducted between March 15 – July 15. Image: Second Condition Work AEA Work Mill be conducted between March 15 – July 15. Image: Second Condition Work AEA Work Moring Low Image: Second Condition Second Condition No work AEA Image: Second Condition Second Condition Image: Second Condition Second Condition ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 Image: Second Condition All dimensions core in millimeters unless otherwise shown.	5		Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall I				
Witzensoor Witzensoor Work AFEA Load line Under sufficient to provide Witzensoor NON WORK AFEA PLN Under sufficient to provide NON WORK AFEA Very work witzensoor PLN Under sufficient to provide NON WORK AFEA Very work witzensoor PLN Under sufficient to provide SECTION A-A NOTES SECTION A-A NOTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Nov 2021 Rev 3 Underside sufficient to provide Interprovincial Standard Drawing Nov 2022 Rev 3 Underside sufficient to provide Interprovincial Standard Drawing	6						
Water Change in direction Floatation Work AREA Load line Maging back WaterBoDY Now WORK AREA PLAN Te down Water Formed and heat seciled or sewn seam Bollost (Note 1) Water Load line Formed and heat Seciled or sewn seam Water Maoring back Formed and heat Seciled or sewn seam Water Maoring line Turbidity curtain Seciled or sewn seam Water Maoring line Section A – A Section A – A NOTES: 1 Additional ballast may be required depending on local conditions. All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 Turbidity Curtain InterBidity Curtain InterBidity Curtain InterBidity Curtain InterBidity Curtain	7	7.	No in water work will be conducted between March 15 — July 15.				
Work AREA Load line Working buoy WaterBODY Now Work AREA PLAN Water Mooring buoy Now Work AREA Very Bolisoning of Urbidity curtain PLAN Water Mooring buoy Load line Very Bolisoning of Urbidity curtain Formed and heat sected or sewn seam Water Mooring buoy Formed and heat sected or sewn seam Water Mooring buoy Formed and heat sected or sewn seam Water Mooring buoy Formed and heat sected or sewn seam Water Mooring line Turbidity curtain Bottom of wiethoody Section A – A NOTESI 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN Understand Understand Understand Understand							
Work AREA Lood line Work AREA Lood line Work oring buay WaterBODY Now WORK AREA PLAN Work oring buay Valended Unbidity curtain PLAN Bottom of Formed and heat Secied or seen seem Secied or seen seem Work origination of Turbidity curtain Bottom of Turbidity curtain Bottom of Section A – A NOTESI 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN TURBIDITY CURTAIN TURBIDITY CURTAIN							
Work AREA Lood line Work AREA Lood line Work oring buay WaterBODY Now WORK AREA PLAN Work oring buay Valended Unbidity curtain PLAN Bottom of Formed and heat Secied or seen seem Secied or seen seem Work origination of Turbidity curtain Bottom of Turbidity curtain Bottom of Section A – A NOTESI 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN TURBIDITY CURTAIN TURBIDITY CURTAIN							
Water Mooring buoy Norving buoy Norving buoy Norving buoy Variationing of Urbidity curtain PLAN Formed and heat Water Mooring buoy Load line Formed and heat Sected or sewn seam Sected or sewn seam Water Mooring line Urbidity curtain Water Mooring buoy Load line Formed and heat Sected or sewn seam Sected or sewn seam Group of the sected or sewn seam Water Mooring line Iom max Bottom of Typ Section A – A NOTES: 1 Additional boliast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 TURBIDITY CURTAIN Image: Sected or sewn seam Image: Sected or sewn seam							
Mooring buay Type Mooring buay Not work AREA PLAN Not WORK AREA PLAN Wider Mooring buay Inter down Formed and heat Bellest (Note 1) Wider Formed and heat Orego 19:261 Formed and heat Bellest (Note 1) Wider Formed and heat Orego 19:261 Formed and heat Orego 19:261 Bottom of weterbody Turbidity curtain Formed and heat Orego 19:261 Bottom of weterbody Section A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN Intermediate Intermediate Intermediate Intermediate			Change in direction				
Water Moning uvy PLAN Buildet (Note 1) Water Mooring buoy Load line Formed and heat sector or seven secon Woring line Image: Sector of seven secon Water Water Water Wooring line Image: Sector of seven secon Water Existing ground sector of seven secon Water Bottom of Image: Sector of seven secon Sector of seven secon Water Existing ground sector of seven secon Adjustment lines SECTION A-A SECTION A-A NOTES: NOTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 I Additional ballast may be required depending on local conditions. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN Image: Sector of Seven secon Image: Second s							
PLAN Water Mooring buoy Formed and heat secled or sewn seam OPSD 219.281 Water Mooring line Water Secured on theat secled or sewn seam OPSD 219.281 Water Line Bottam of Water Line Bottam of Water Line Secured on theat secured on theat secured or sewn seam OPSD 219.281 Turbidity curtain Secure on A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. Contario Provincial Standard Drawing TURBIDITY CURTAIN			Anchor sufficient to provide NON WORK AREA				
Load line secled or sewn seam OPSD 219.261 Woter Existing Bottom of Water Existing Gersen seam OPSD 219.261 Turbidity curtain geosynthetic SECTION A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown.							
Mooring line 10m max Formed and heat sealed or sewn seam OPSD 219.261 Bottom of waterbody 10m max Turbidity curtain geosynthetic Bottom of waterbody SECTION A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN Image: standard			Water Mooring buoy Formed and heat sealed or sewn seam				
Mooring line Image: Secied or sewin seam OPSD 219.261 Bottom of waterbody Image: Secied or sewin seam OPSD 219.261 Adjustment lines SECTION A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 TURBIDITY CURTAIN Image: Secied or sewin seam OPSD 219.261 Image: Secied or sewin seam OPSD 219.261							
Bottom of waterbody Image: section a - a Adjustment lines SECTION A - A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 TURBIDITY CURTAIN Image: section a - a			Mooring line line ground sealed or sewn seam line ground surface				
Adjustment lines Adjustment lines SECTION A-A NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. TURBIDITY CURTAIN			Turbidity curtain geosynthetic				
Typ SECTION A=A NOTES: 1 1 Additional ballast may be required depending on local conditions. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3							
NOTES: 1 Additional ballast may be required depending on local conditions. A All dimensions are in millimeters unless otherwise shown. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 							
depending on local conditions. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3 A All dimensions are in millimeters unless otherwise shown. TURBIDITY CURTAIN			NOTES:				
unless otherwise shown. TURBIDITY CURTAIN			depending on local conditions. ONTARIO PROVINCIAL STANDARD DRAWING Nov 2022 Rev 3				
			unless otherwise shown.				

