

August 30, 2022

Re: Request for Quotation – Asphalt Repair and Paving (RFQ-EC-PW-22-04)

Brief Description of Work:

(A) Patching and overlays

The Township requires a contractor to make all final preparations for paving and to pave the areas in attached form located in the Township of Edwardsburgh Cardinal. Township staff will cut and remove the sections of existing asphalt, where applicable, provided that one week notice is given prior to commencement of work.

The minimum thickness of asphalt is stipulated in the attached form. The new pavement must be compacted and as seamless as possible to meet surrounding existing asphalt grade and slope. OPSS to be followed. The unit cost of all labour, material, equipment and mobilization required to complete the work is to be included in the cost/metric tonne of HL3 HBC material used provisional to a total maximum of 110 metric tonnes.

(B) Cedar Grove Road and Scott Road

Cedar Grove Road and Scott Road require a Pad and Pave treatment. The treatment for Cedar Grove will begin at the westerly border of Edwardsburgh Cardinal Township where Cedar Grove meets Augusta Township and proceed to the east. Scott Road will begin at County Road 22, or as directed by the Township's Public Works Manager, and proceed east. Due to the uncertainty of the quantity of HBC required for the treatment, the unit cost of all labour, material, equipment and mobilization required to complete the work is required to be included in the cost/metric tonnes of HL3 HBC material used provisional to a total maximum of 400 metric tonnes for Cedar Grove and 150 metric tonnes for Scott Road. Ruts and imperfections will be padded with HL3 HBC and followed with a final continuous surface pavement of 25mm of HL3 which will be included in the total unit cost and maximum total tonnage.

The contractor will be responsible for providing all traffic control and applicable health and safety requirements in the performance of the work.

The Township reserves the right to reduce or expand the scope, subject to budget. The lowest or any quotation may not necessarily be accepted. For more information or viewing, please contact the Public Works Manager, Chris LeBlanc at (613)658-3055 x7 or cleblanc@twpec.ca.


Deadline for Quote Submission: Tuesday September 13, 2022 at 4:00pm local time.

Anticipated Award: Monday September 19, 2022.

Deadline for Work Completion: Monday October 31, 2022.

Please complete attached form and submit. Submissions can be sent to gshaw@twpec.ca or via fax at 613 658 2164 until Tuesday September 13, 2022 at 4:00pm local time.

Thank You

A handwritten signature in black ink, appearing to read 'Gord Shaw', with a horizontal line underneath it.

Gord Shaw
Director of Operations
Township of Edwardsburgh Cardinal

Contractor Information



EDWARDSBURGH CARDINAL

Phone: 613-658-3055
Fax: 613-658-3445
Toll Free: 866-848-9099
E-mail: mail@twpec.ca

P.O. Box 129,
18 Centre St.
Spencerville, Ontario
K0E 1X0

Company Name	
Contact Name	
Mailing Address	
Telephone Number	
Facsimile Number	
E-Mail Address	

(A) Patching and overlays

Location	Rough Measurements			Depth mm	Cost / Mt
	Width(m)	Length (m)	Rough Sq. m		
Armstrong Rd	6.4	275	1760	25	

(B) Cedar Grove Pad and Pave: All-inclusive cost per metric tonne of HL3 HBC

Total cost/Mt \$ _____

Scott Road Pad and Pave: All-inclusive cost per metric tonne of HL3 HBC

Total cost/Mt \$ _____

Name and Position

Signature

Date