



EDWARDSBURGH CARDINAL

TENDER NO. EC-PW-25-08

Reconstruction of Waddell Street

DATE: May 30th, 2025

ADDENDUM #1 - FINAL

This addendum will become part of the Tender No. EC-PW-25-08.

PART 1 – CLARIFICATIONS AND DOCUMENT REVISIONS

C1. An item and special provision have been added to the project for pre and post construction CCTV of the existing sanitary system. The intent is to confirm the condition of the existing sanitary sewer before and after construction. An updated bid form and revised special provision pages have been attached to this addendum.

C2. An item has been added to account for a small amount of concrete sidewalk reinstatement at the tie-ins to existing. An item has also been added to provide tactile walking surface indicators at these reinstatements. An updated bid form has been attached to this addendum.

PART 1 – QUESTIONS RECEIVED

Q1. Can a Geotech report be provided?

R1. There is no geotechnical report available for this project.

Q2. Can the excess soils characterization report be provided in accordance with O.Reg 406/19 ? alternatively can the township provide a disposal location if the SCR is not available?

R2. An SCR is not available. As per Section 180.07.03 of the Special Provision for Excess Soil Management, excess soils shall be disposed of at the property across from 1225 Scott Road, Cardinal, Ontario.

(A signed copy of this addendum must be included in Tender submission.)

I /WE hereby acknowledge receipt of this addendum.

(Signature of Contractor)

(Company Name)

PLEASE SIGN AND INSERT WITH TENDER SUBMISSION

Itemized Bid Form

Item No.	OPSS, SP	Item Description	Unit	Quantity	Unit Price (\$)	Total Bid (\$)
1	SP	Mobilization/Demobilization	LS	1		
2	206, SP	Earth Excavation, Grading	m ³	603		
3	206	Rock Excavation, Grading (Provisional)	m ³	20		
4	310	Tack Coat	m ²	1081		
5	310, SP	Hot Mix Asphalt Miscellaneous	m ²	81		
6	310, SP	Hot Mix HL3 Asphalt, PGAC 58-34	t	254		
7	314	Granular A	t	608		
8	314	Granular B, Type II	t	785		
9	353	Concrete Curb & Gutter	m	263		
10	353	Concrete Gutter Outlets	each	1		
11	405	Pipe Subdrain	m	240		
12	407	600 mm x 600 mm Concrete Catch Basins, Ditch Inlets	each	3		
13	407	1200 mm Maintenance Holes	each	2		
14	407, SP	Breaking into Manholes, Catch Basins, Ditch Inlets, Culverts and Sewers	each	1		
15	408	Rebuilding Maintenance Holes	each	1		
16	408	Adjusting Maintenance Holes and Water Valves	each	5		
17	410, SP	300 mm HDPE Storm Pipe	m	105		
18	510, SP	Removal of Asphalt Pavement, Full Depth	m ²	1047		
19	510, SP	Removal of Asphalt Pavement, Partial Depth	m ²	24		
20	510, SP	Removal of Pipes and Culverts	m	95		



21	510, SP	Removal of Concrete Sidewalk	m ²	185		
22	510, SP	Removal of Maintenance Holes, Catch Basins, Ditch Inlets and Valve Chambers	ea	4		
23	706	Temporary Traffic Control Signs	LS	1		
24	710, SP	Pavement Marking	LS	1		
25	802	Topsoil, Imported	m ³	38		
26	803	Sod	m ²	233		
27	805, SP	Temporary Erosion and Sediment Control Measures	LS	1		
28	180, SP	Management of Excess Soil	m3	894		
29	410, SP	Removal and Replacement of Existing 100 mm Sanitary Services (Provisional)	ea	1		
30	409, SP	CCTV Inspection	LS	1		
31	351	Concrete Sidewalk	m ²	6		
32	351	Tactile Walking Surface Indicators	ea	2		

The Township of Edwardsburgh/Cardinal has the right to eliminate any or all sections of the project (in the itemized bid form) at any time after Tender Closing without penalty.

The Tenderer hereby offers to complete the work specified for Tender No. EC-PW-25-08 for the following prices:

Sub-Total	\$
HST	\$
TOTAL COST	\$

HST REGISTRATION NO. _____

6. I/We agree that this offer is to continue open to acceptance until the formal Contract is executed by the successful tenderer for the said work or until forty-five (45) calendar days after the said opening, whichever event first occurs; and that the Corporation may, at any time within that period, without notice, accept this tender whether any other tender has been previously accepted or not.
7. I/WE agree that if I/WE withdraw this tender before the Council of the said corporation shall have considered the tenders and awarded the Contract, the amount of the deposit accompanying this tender shall be forfeited to the Corporation.



410.09 MEASUREMENT FOR PAYMENT

410.09.01.02 Service Connections

Clause 410.09.01.02 is deleted in its entirety and replaced by the addition of the following:

For measurement purposes, a count shall be made of the number of services replaced from the main to the property line. Payment shall be by each and shall include the removal and replacement of the existing service.

**Special Provision
Item #30
CCTV Inspection**

The provisions of OPSS 409 shall apply to this item with the following amendments:

SCOPE

This item shall cover a CCTV inspection of the existing sanitary sewer and laterals at each of the following milestones:

- a) Prior to any construction activities.
- b) Immediately prior to completion of paving.

The intent of this work shall be to assess for any damage to the existing sanitary main or laterals that may have occurred during construction.

409.07.02 Pipeline Cleaning

Clause 409.07.02 is amended by the addition of the following:

Sewers shall be cleaned and flushed by the Contractor immediately prior to CCTV inspection.

409.09 MEASUREMENT FOR PAYMENT

Clause 409.09 is deleted in its entirety and replaced by the addition of the following:

Payment for CCTV inspection shall be by lump sum and shall be inclusive of all work, including cleaning and flushing, as indicated by OPSS 409. The Contractor shall assume that the entirety of the sanitary main on Waddell Street will require inspection, as well as all service laterals.

Payment by lump sum shall be inclusive of completing the CCTV inspections at all stated milestones.



409.10.01 BASIS OF PAYMENT

Clause 409.10.01 is amended by the addition of the following:

Payment shall be made at the following intervals for CCTV inspection:

- 50% upon completion of the deliverables, including Final Documentation, for the pre-construction inspection.
- 50% upon completion of the deliverables, including Final Documentation, for the pre-paving inspection.

